BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P.Bengaluru-64

Original/Duplicate

APPROVED SCHEDULE-'B'

NAME OF THE WORK : Improvements Roads And Drains At Ambedker Nagara Slum And Kanaka Nagara Slum In Ward No.04

SI	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	787.44	220.40	Rupees Two Hundred Twenty And Paise Forty Only
2	Removing And Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	613.60	111.30	Rupees One Hundred Eleven And Paise Thirty Only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	321.01	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	80.58	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only

Signature Of The Contractor

Executive Engineer-4
KRIDL, BBMP, Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangaluru 64

Scanned with CamScanner

	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
5	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.	Tonne	2.02	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six And Paise Ninety Eight Only
6	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	212.70	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
7	Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete.	No's	966.00	477.00	Rupees Four Hundred Seventy Seven Only
8	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	174.00	39.22	Rupees Thirty Nine And Paise Twenty Two Only
9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications	Sqm	174.00	84.80	Rupees Eighty Four And Paise Eighty Only
10	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	367.95	2001.28	Rupees Two Thousand One And Paise Twenty Eight Only

Signature Of The Contractor

Executive Engineer-4
KRIDL, BBMP, Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangaluru 64

Scanned with CamScanner

	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
11	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum)	Cum	546.76	5210.96	Rupees Five Thousand Two Hundred Ten And Paise Ninety Six Only
12	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	3671.60	72.08	Rupees Seventy Two And Paise Eight Only
13	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg I sqm using mechanical means complete as per specifications.	Sqm	970.20	36.04	Rupees Thirty Six And Paise Four Only
14	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen	Cum	38.91	7721.04	Rupees Seven Thousand Seven Hundred Twenty One And Paise Four Only

Signature Of The Contractor

Executive Engineer-4
KRIDL, BBMP, Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangaluru 64

Scanned with CamScanner

	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
15	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	970.20	5.30	Rupees Five And Paise Thirty Only
16	Providing and applying tack coat using 80/100 grade bitumen(VGIO) on the prepared black topped surfaces at 2.5 kg per 10sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	970.20	14.84	Rupees Fourteen And Paise Eighty Four Only
17	Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509 - using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4 % VG-30 BitumenItem No.21.22.6)	Cum	62.33	8980.32	Rupees Eight Thousand Nine Hundred Eighty And Paise Thirty Two Only
18	Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface- providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface to level, uniform and free from streaks and holes complete as per specifications.	Sqm	35.10	454.74	Rupees Four Hundred Fifty Four And Paise Seventy Four Only

Signature Of The Contractor

Executive Engineer-II
KRIDL, BBMP, Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangaluru 64

Scanned with CamScanner